



## Datenblatt

M.I.T.T.E.S engineering GmbH  
Oberschaden 32  
4070 Puppung  
Austria

### MOBILE LOADBANK 2300kVA Resistive/Inductive



Load Ratings (continuous):	Hz	50	60
	KVA (kW)	2300 (1850) @ 400V	2943(2468)@460V3ph
	PF	0.80	0.84
Loading Increments:	KVA	33.0 @ 415V	37.0 @ 460V
Remote Control:	10m + 50m Cable for Remote Control		
Auxiliary Supply:	400V, 50Hz , 63A CEE Plug		
Load Terminals:	Busbar M12		
Overall Dimensions:	Length:	6.10m	
	Width:	2.44m	
	Height:	2.60m	
Weight:	10.600 kg		